



## REPAIR OF A TAXIWAY

### PROBLEM

Around the drainage channels there was a delamination of the concrete top layer. This caused a risk that loose pieces of concrete were sucked into the engines of the aircraft.

### SOLUTION

The affected surface layer was milled. Subsequently, all dust and loose material was taken away. CEMPRIME AC was applied in preparation of the final layer.

On one night the entire taxiway was repaired with CEMTOP 360.

### USED PRODUCTS

[CEMPRIME AC](#) : Universal primer for cementitious screeds.

[CEMTOP 360](#) : Very heavy duty floor system for use in agricultural and industrial buildings.



**cemprime**  
**cemtop**

### PROJECT DETAILS

LOCATION	Atatürk airport—Istanbul (Turkey)
DATE OF EXECUTION	November 2009
ENGINEERING	Airport authorities
CONTRACTOR	eko GRUBU

More info?  
[www.cemart.eu](http://www.cemart.eu)